



Framing Bid Sheet

The framing contractor shall provide all labor and equipment necessary to complete the following:

Walls

- Layout wall according to plans and specifications making sure walls are squared and to correct dimensions.
- Frame walls using provided materials.
- Crown all studs and components the same direction to prevent wall bulges.
- Cull materials if of inferior quality.
- Plumb and line walls with a high degree of accuracy.
- Sheath and wrap with provided materials.

Ceiling and Roof System

- Install provided ceiling and roof materials to detailed specifications.

Windows and Doors

- Install windows and doors plumb, level, and square to insure proper operation of unit.

Sidings and Exterior Trims

- Install all sidings and trims to manufacturer's specifications and plan design.
- Install provided flashings and seals.

Clean-Up

- Maintain a clean, and safe worksite daily.

Please provide bid reflecting all labor and equipment required to complete the framing portion of the build. Break out each category by cost per square foot.

Please reference which site you are bidding, include references, licenses and certifications. For more, including insurance requirements and accounts payable schedule, visit greencountryhabitat.org/bids.